

III. TECHNICAL SPECIFICATIONS

DIVISION 46

TREATED TIMBER PILES

- 46.01 SCOPE:** The Contractor shall furnish all materials, equipment and labor necessary to disconnect and reinstall piles in accordance with accompanying plans and applicable section of Virginia Department of Transportation, Road and Bridge Specifications (VDOT) dated January 1991, except Measurement and Payment shall be in accordance with Division 46.04.
- 46.02 MATERIALS:** All materials shall be new and shall be furnished as per plans and Virginia Department of Transportation Road and Bridge Specifications.
- 46.03 EXECUTION:** Repairs are to include disconnecting, unwrapping, reconnection, rewrapping, necessary hardware, pulling piles, re-driving pulled piles or re-driving furnished new piles in original designed position and all incidental construction. Disposal of replaced materials will be the Contractor's responsibility. Piles are to be inspected by representatives of the City upon extraction to determine if a new pile will be furnished.
- 46.04 MEASUREMENT AND PAYMENT:** Cost of all materials, labor and equipment as well as incidental expenses shall be included in the unit price for repairs and shall be measured and paid for as follows:
- A. Existing Piles pulled and re-driven completed and accepted will be paid for at the unit price bid per lineal foot specified in the proposal.

No separate payment will be made for disconnection, unwrapping, reconnection and rewrapping of piles which will be considered incidental to the contract price per lineal foot as specified in the unit price proposal.
 - B. To furnish treated timber piles for damaged piles will be paid for at the unit price bid per lineal foot specified in the proposal.

No separate payment will be made for the removal and disposal of replaced materials which will be considered incidental to the contract price per lineal foot as specified in the unit price proposal.