

III. TECHNICAL SPECIFICATIONS

DIVISION 48

PLATFORM, WALKWAY, HANDRAIL AND POSTS

- 48.01 SCOPE:** The Contractor shall furnish all materials, equipment and labor necessary to disconnect and reinstall treated timber wales in accordance with accompanying plans and applicable sections of Virginia Department of Transportation, Road and Bridge Specifications (VDOT) dated January 1991, except Measurement and Payment shall be in accordance with Division 48.04.
- 48.02 MATERIALS:** All materials shall be new and shall be furnished as per accompanying plans and Virginia Department of Transportation Road and Bridge Specifications.
- 48.03 EXECUTION:** Repairs are to include disconnecting, reinstallation of new platform, walkway, handrail and posts necessary hardware and all incidental construction. Disposal of replaced materials will be the Contractor's responsibility.
- 48.04 MEASUREMENT AND PAYMENT:** Cost of all materials, labor and equipment as well as incidental expenses shall be included in the lump sum price for repairs. Platform, walkway, handrail and posts repairs will not be measured and paid for as such. Items completed and accepted will be paid for at the price bid per lump sum specified in the proposal.

No separate payment will be made for removal and disposal of replaced materials which will be considered incidental to the contract price per lump sum as specified in the lump sum price proposal.