

III. TECHNICAL SPECIFICATIONS

DIVISION 14

BEDDING MATERIAL (BOX CULVERT)

- 14.01 SCOPE:** The Contractor shall be required to furnish all material, labor, and equipment necessary to place bedding material for box culvert construction at the locations and depths shown on the plan and in accordance with the following provisions.
- 14.02 MATERIALS:** Crusher run aggregate shall be size number 25,26 or 57 and consist of crushed stone, slag, or crushed gravel and conform with Sections 205 of the VDOT Road and Bridge Specifications for Grading, Atterberg Limits, Soundness, and Abrasion Loss.
- 14.03 EXECUTION:** Bedding Material shall be placed in a trench relatively free of water on top of acceptable local material or Select Borrow II if shown on the plans or specified by the Engineer. Bedding material shall be lightly and uniformly compacted and will not be subject to the requirements of Section 7 of the General Conditions Part II for increased or decreased quantities.
- 14.04 MEASUREMENT AND PAYMENT:** Bedding material for box culverts shall be field measured at the square yards in place at the depth shown on the plans or directed by the Engineer. If additional depths of bedding material are required it will be increased by the Engineer at six (6) inch intervals. Increased depths resulting from field changes will increase the unit price quantities linearly. Payment will be made at the contract price for square yards per depth as specified in the Unit Price Table. Bedding material placed outside the limits shown on the plans or specified by the Engineer will not be measured. Bedding material for headwall and endwall construction when specified on the construction plans or directed by the Engineer in the field will not be measured and paid for as such, but will be considered incidental to the price per each as per the Unit Price Table.