

Division 25: Chain Link Fence

- 25.01** **SCOPE:** This work shall consist of the removal of existing fence and installation of new fence in accordance with VDOT Road and Bridge Specifications Section 509 and with the lines shown on the plans.
- 25.02** **MATERIALS:** All existing fence must be utilized. Any new materials shall conform to Section 507.02 of the VDOT Specifications, and all costs thereof must be included in the unit price for standard chain link fence.
- 25.03** **EXECUTION:** Construction shall conform to Section 507.03 (a) for Standard Chain Link Fence.
- 25.04** **MEASUREMENT AND PAYMENT:** Fence will be measured in lineal feet of fence fabric, complete-in-place. Payment will be per lineal foot for both new and removed fence at the unit prices specified in the Unit Price Table. The prices for new fence shall include full compensation for all work required to clear and level the terrain at the fence and disposal of surplus material. The prices for removal of fence shall include full compensation for the removal and disposal of all fence.

25.05