

DIVISION ~~63~~ 68

RIGHT-OF-WAY RESTORATION AND TEMPORARY CONSTRUCTION REQUIREMENTS

68.01 SCOPE: All construction work shall be performed to minimize negative impact on the general public.

68.02 EXECUTION:

- A. Contractor shall be required to maintain the existing travel lanes at all times unless specific lane closures are in accordance with an approved traffic control plan.
- B. Contractor shall be responsible for complying with Division 3 of the General Technical Specifications for Allaying Dust.
- C. Contractor shall provide noise abatement measures to ensure compliance with the City noise ordinance, Chapter 16A.
- D. Once work has begun in the right-of-way it shall continue without interruption (during normal work hours) weather permitting until completed unless otherwise approved by the Engineer.
- E. All paved areas disturbed by construction shall be backfilled in accordance with the approved pavement section and asphalt concrete or cold mix shall be installed prior to completion of work on any day unless otherwise approved by the Engineer. Surface tolerance shall be installed and maintained in accordance with City of Chesapeake Standard PC-1 or until final acceptance of public improvements by the City.
- F. Contractors to provide temporary drainage as required to maintain existing drainage.

68.03 MEASUREMENT AND PAYMENT: Unless otherwise provided in the contract documents no separate payment shall be made. Cost of this work shall be considered incidental to the various related bid items.