

# CITY OF CHESAPEAKE

## INVITATION FOR BID

### ADDENDUM NO. 1

ISSUE DATE: February 25, 2010 IFB No. 10095

TITLE: Battlefield Golf Club Water Project  
Murray Drive & Whittamore Road

ISSUED BY: City of Chesapeake  
Purchasing Division  
306 Cedar Road, 5th Floor  
Chesapeake, Virginia 23322

DEPARTMENT: Public Utilities

---

#### **THE ATTACHMENT BY REFERENCE IS HEREBY INCORPORATED IN THIS CHANGE.**

This Addendum clarifies and modifies the Contract Documents and Special Provisions dated December 2009 as noted below. This Addendum is hereby incorporated into the Contract Documents. Bidder shall acknowledge receipt of this Addendum in the space provided on the modified Bid Form. Failure to do so may subject Bidder to disqualification.

#### **I. MODIFICATIONS**

##### **A. Construction Plans, Sheets C-1 thru C-4,**

Murray Drive addresses 1104, 1108, 1112, 1116, 1120, 1204, 1208, 1212, 1216 and 1220. The construction plans show a PROPOSED FIBER OPTIC CABLE BY VERIZON adjacent to the right of way over several of these addresses. This facility has been installed and is located behind the curb line with a distance that varies from 2 to 7 feet. The contractor is to remove this facility within the above limits as part of the water project. After project completion, Verizon will reinstall their facilities.

##### **B. Construction Plan, Sheet C-4 thru C-6,**

Murray Drive addresses 1304, 1308, 1312, 1316, 1320 and 1324. The construction plans show a PROPOSED FIBER OPTIC CABLE BY VERIZON adjacent to the right of way. This facility has been installed and is located approximately 2 to 7 feet behind the curb line. The underground installation is 2-PVC conduit with a direct bury fiber optic line. This line is active.

The contractor is to coordinate with:

Deborah Ballard  
Engineering/OSP Engineering  
Verizon  
1.757.482.8089  
765 S. Battlefield Blvd.  
Chesapeake, Va. 23322

Initial contact is to be made at least 4-weeks prior to working within the above limits. The contractor is to include in his unit price bid for 10-inch water main the cost of coordination with Verizon and additional effort required to maintain services and assist Verizon in protecting these facilities.

The bidder shall visit the site and make themselves aware of the locations of these facilities prior to preparing the bid.

##### **C. Construction Plans, Sheet C-1 thru C-6,**

The typical location of the 10-inch water line is shown as 2 ½ feet behind the face of curb.

At each location the distance of 2 ½ feet is revised to 4-feet.  
At station 11+33 the horizontal alignment shall be deflected by joint deflection from this 4-foot distance to tie to the stub placed along Murray Drive under a previous contract.

II. CLARIFICATIONS

A. Construction Plans, Sheet C-1 thru C-6,

Trees along the south side of Murray Drive.

1. Trees on private property are to remain.
2. Trees on the right of way line are to remain and be protected.
3. Trees indicated with tree protection symbol are to be protected.
4. Trees within the right of way not protected by above criteria are to be removed.

B. Construction Plans, Sheet D-2,

Details with notes titled: PAVEMENT REPLACEMENT

The following clarification is given.

Item II

If the installation of the water line along Whittamore does not damage the existing pavement outside of the limits of the utility trench pavement patching, the utility trench pavement patching will terminate with the finish grade of the BM-2 at the current finish grade of the existing pavement. The entire width and length of Whittamore as defined on the plans will then be overlaid with 2-inches of SM-2a.

Item III

If as a result of the water line installation the pavement in Whittamore is damaged to the extent that the pavement must be removed and replaced, it will be removed and replaced as PAVEMENT REPAIR. The finish grade of the BM-2 will match the current grade of the existing pavement. The entire width and length of Whittamore as defined on the plans will then be overlaid with 2-inches of SM-2a.

The quantities shown on the bid form account for the maximum PAVEMENT REPLACEMENT (Item III) and complete overlay of Whittamore Road.

---

**Note:** A signed acknowledgment of this addendum must be received at the location indicated on the RFP either prior to the proposal due date and hour, or attached to your proposal. Signature on this addendum does not substitute for your signature on the original proposal document. The original proposal must be signed.

---

NAME AND ADDRESS OF FIRM:

\_\_\_\_\_ Date: \_\_\_\_\_  
\_\_\_\_\_ By: \_\_\_\_\_  
\_\_\_\_\_ Name: \_\_\_\_\_ **(Signature In Ink)**  
\_\_\_\_\_ **(Please Print)**  
\_\_\_\_\_ Zip Code: \_\_\_\_\_ Title: \_\_\_\_\_

ALL OTHER TERMS, CONDITIONS, AND SPECIFICATIONS SHALL REMAIN UNCHANGED.

ALL INQUIRIES FOR INFORMATION SHOULD BE DIRECTED TO LAVERA TOLENTINO, BUSINESS SYSTEMS ANALYST, PHONE: (757) 382-6359, FAX: (757) 382-6900, Email: [ltolenti@cityofchesapeake.net](mailto:ltolenti@cityofchesapeake.net)

**END OF ADDENDUM NO. 1**