

**Division 47: Treated Timber Wales**

- 47.01 SCOPE:** The Contractor shall furnish all materials, equipment and labor necessary to disconnect and reinstall treated timber wales in accordance with accompanying plans and applicable sections of Virginia Department of Transportation, Road and Bridge Specifications (VDOT) dated January 1991, except Measurement and Payment shall be in accordance with Division 47.04.
- 47.02 MATERIALS:** All materials shall be new and shall be furnished as per accompanying plans and Virginia Department of Transportation Road and Bridge Specifications.
- 47.03 EXECUTION:** Repairs are to include disconnecting, reinstallation of new wales splicing, necessary hardware and all incidental construction. Disposal of replaced materials will be the Contractor's responsibility.
- 47.04 MEASUREMENT AND PAYMENT:** Cost of all materials, labor and equipment as well as incidental expenses shall be included in the unit price for repairs and shall be measured and paid for as follows:
- A. Treated timber wales completed and accepted will be field measured on the front from joint opening to joint opening. The length so determined will be paid for at the unit price bid per lineal foot specified for each size in the proposal.

No separate payment will be made for the removal and disposal of replaced materials which will be considered incidental to the contract price per lineal foot as specified in the unit price proposal.

