

DIVISION ~~62~~ 67

DETOUR

- 67.01 SCOPE:** The Contractor shall furnish all materials, equipment and labor necessary to install and maintain all necessary traffic control signs to include those necessary for the detour route in accordance with accompanying plans and applicable sections of these Contract Documents.
- 67.02 MATERIALS:** All materials shall be furnished as per accompanying plans and Contract Documents, Supplementary Conditions, Part One, Section 9 and other applicable sections.
- 67.03 EXECUTION:** Detour is to include installation, covering or temporary removal, maintenance and permanent removal of necessary traffic control signs. Time restrictions on detours may be specified on the plans or other sections in the Contract Documents.
- 67.04 MEASUREMENT AND PAYMENT:** Cost of all materials, labor and equipment as well as incidental expenses shall be included in the lump sum price for detour. Installation and Maintenance Detour will not be measured and paid for as such. Items completed and accepted will be paid for at the price bid per lump sum specified in the proposal.